

McTeague Construction Co., Inc.

POSPOSAL

City of Boynton Beach
222 N.E. 9th Ave
Boynton Beach FL 33435

March 30 2017

Attn: Gail Mooyz

Project: Hester Center C.O. 1

1. Remove all stucco and plywood on existing entrance and east side of Hester center
2. Install 5/8 plywood on existing metal frames
3. Install 30lb felt on plywood
4. Install wire lath and stucco over plywood
5. Remove and install metal cap on parpit wall
6. Install new 2x4 bucks for windows
7. Additional time required 20 days

Total

\$ 19,100.00

Michael H McTeague



McTeague Construction Co Inc.