

**F-06-2021 - Harvey Oyer Park (Precast Privacy Wall) (2010 N Federal Hwy., Boynton Beach, FL 33435)**  
**RFQ NO. 028-2511-20/RW PRE-QUALIFICATION OF CONTRACTORS FOR MINOR CONSTRUCTION SERVICES - BID FORM**

| ITEM | DESCRIPTION   | QTY | UNIT | Grand Total |
|------|---|-----|------|-------------|
|      | Supply all labor, material, tools, equipment, hardware, supplies, and supervision per the following scope, (Job Site to be picked up and clean for the duration of the project). Perform all work in a professional and courteous manner. Protect any city property for the duration of the project. Contractor is responsible for maintaining a safe and secure work area. <u>ALL PRODUCT SPECS SHALL BE SUBMITTED FOR APPROVAL.</u> |     |      |             |
|      | <b>Install new precast wall per attached pdf plans.</b>   |     |      |             |
|      | DUMPSTER: Contractor must use a City of Boynton Beach Dumpster and is responsible for all fees, delivery and pick-up, call (561)-742-6200 to schedule.  |     |      |             |
|      | CONTRACTOR SHALL ADHERE TO ALL CITY OF BOYNTON BEACH CONSTRUCTION TIMES AND NOISE ORDINANCES.   |     |      |             |
|      | <b>SCOPE #1</b>   |     |      |             |
|      | <b>Precast Wall Installation</b>  |     |      |             |
|      | Prepare Site with any necessary safety measures   |     |      |             |
|      | Remove and dispose of all existing vegetation on south side of property line-any vegetation in conflict with or within 3' ft of the proposed wall location  |     |      |             |
|      | Grade as per survey, elevations - <b>Provide Survey for Property Line Staking</b>   |     |      |             |
|      | Compact and Test (LRB 98% min.) at all column footer locations  |     |      |             |
|      | Construct concrete footer locations   |     |      |             |
|      | Take concrete cylinders every 50 cy or each days production for all in situ placed concrete   |     |      |             |
|      | Install Precast columns and wall sections (Center line of wall shall be 2'-3" offset from Property line)  |     |      |             |
|      | Prep, prime & Paint Precast Wall -both sides (2 coats - "MAB5106-" Windridge")  |     |      |             |
|      |   |     |      |             |
|      | <b>NOTES:</b>   |     |      |             |
|      | Provide all QA/QC reports from Precast Plant Mfr  |     |      |             |
|      | Provide all density and cylinder compressive reports for job site concrete  |     |      |             |
|      | Provide mill certs for all rebar used in footings   |     |      |             |
|      | Layout wall as per plan to avoid FPL poles and sewer MH existing locations  |     |      |             |
|      |   |     |      |             |
|      | <b>Site Restorations Plan</b>   |     |      |             |
|      | Remove all trash and debris   |     |      |             |
|      | Restore all Soded areas   |     |      |             |
|      |   |     |      |             |
|      | <b>ADDENDUM #1</b>  |     |      |             |

**Scope 1 and Alternate Pricing** Contractor is responsible for any repairs to the irrigation system, this shall include but not be limited to; sprinkler lines, sprinklers heads, sprinkler valves, sprinkler boxes. There may be underground lines along the fence that supply other areas in the park. Anything damaged during construction of the new wall shall be repaired at the contractors expense.

**Alternate Pricing** The above scope will be followed with a change near Federal Highway existing block wall. The new Precast wall shall terminate and return into the existing block wall.  
 Pressure wash and paint the southside of the existing to remain block wall near Federal Highway. ("MAB5106-" Windridge")

**Submittal Date and time is changed to Thursday, April 8th at 2:00pm**

GRAND TOTAL PRICE - Scope 1 (Lump Sum) \$ - 137,000.00

GRAND TOTAL PRICE - Alternate Pricing (Wall change at Federal Highway) (Lump Sum) \$ - 132,000.00

Name of Firm Submitting Bid Proposal \$ - ALIZCO INC

Name of Person Submitting Bid Proposal John To 2911

Name of Person Submitting Bid Proposal

(SIGNATURE)  
 Date: 4/8/21