

F-06-2021 - Harvey Oyer Park (Precast Privacy Wall) (2010 N Federal Hwy., Boynton Beach, FL 33435)

RFQ NO. 028-2511-20/RW PRE-QUALIFICATION OF CONTRACTORS FOR MINOR CONSTRUCTION SERVICES - BID FORM

ITEM	DESCRIPTION	QTY	UNIT	Grand Total
	Supply all labor, material, tools, equipment, hardware, supplies, and supervision per the following scope, (Job Site to be picked up and clean for the duration of the project). Perform all work in a professional and courteous manner. Protect any city property for the duration of the project. Contractor is responsible for maintaining a safe and secure work area. <u>ALL PRODUCT SPECS SHALL BE SUBMITTED FOR APPROVAL.</u>	1	LS	149,996.00
	<i>Install new precast wall per attached pdf plans.</i>			
	DUMPSTER: Contractor must use a City of Boynton Beach Dumpster and is responsible for all fees, delivery and pick-up , call (561)-742-6200 to schedule.			
	CONTRACTOR SHALL ADHERE TO ALL CITY OF BOYNTON BEACH CONSTRUCTION TIMES AND NOISE ORDINANCES.			
	SCOPE #1			
	Precast Wall Installation			
	Prepare Site with any necessary safety measures			
	Remove and dispose of all existing vegetation on south side of property line-any vegetation in conflict with or within 3' ft of the proposed wall location			
	Grade as per survey, elevations - Provide Survey for Property Line Staking			
	Compact and Test (LRB 98% min.) at all column footer locations			
	Construct concrete footer locations			
	Take concrete cylinders every 50 cy or each days production for all in situ placed concrete			
	Install Precast columns and wall sections (Center line of wall shall be 2'-3" offset from Property line)			
	Prep , prime & Paint Precast Wall -both sides (2 coats - "MAB5106-" Windridge")			
	NOTES:			
	Provide all QA/QC reports from Precast Plant Mfr			
	Provide all density and cylinder compressive reports for job site concrete			
	Provide mill certs for all rebar used in footings			
	Layout wall as per plan to avoid FPL poles and sewer MH existing locations			
	Site Restorations Plan			
	Remove all trash and debris			
	Restore all Soded areas			
	ADDENDUM #1			

Scope 1 and Alternate Pricing

Contractor is responsible for any repairs to the irrigation system, this shall include but not be limited to; spinkler lines, sprinklers heads, sprinkler valves, sprinkler boxes. There maybe underground lines along the fence that supply other areas in the park. Anything damaged during construction of the new wall shall be repaired at the contractors expense.

Alternate Pricing	The above scope will be followed with a change near Federal Highway existing block wall. The new Precast wall shall terminate and return into the existing block wall. Pressure wash and paint the southside of the existing to remain block wall near Federal Highway. ("MAB5106-" Windridge")	1	LS	134,256.00
--------------------------	--	---	----	------------

Submittal Date and time is changed to Thursday, April 8th at 2:00pm

GRAND TOTAL PRICE - Scope 1 (Lump Sum)

\$ - 149,996.00

GRAND TOTAL PRICE - Alternate Pricing (Wall change at Federal Highway) (Lump Sum)

\$ - 134,256.00

Name of Firm Submitting Bid Proposal

RPM General Contractors, Inc.

Name of Person Submitting Bid Proposal

Robert P. McTeague, Jr.

Name of Person Submitting Bid Proposal

Robert P. McTeague, Jr.

(SIGNATURE)

Date: 4/8/2021

RPM GENERAL CONTRACTORS, INC.

680 N.E. 26th COURT
POMPANO BEACH, FL 33064
rpmgcinc@aol.com

CGCA # 037314
(954) 785-8900
FAX (954) 785-4070

April 8, 2021

Kristeena Pinto-Purchasing Manager
City of Boynton Beach
100 E. Ocean Avenue
Boynton Beach, FL 33435

PRE-QUAL TASK ORDER #F-06-2021 – Harvey Oyer Park Privacy Wall Project

SUBCONTRACTOR LIST

PRECAST CONCRETE FABRICATION/INSTALL
Precast Wall Systems, Inc.
1888 NW 22nd Court
Pompano Beach, FL 33069
954-973-8488

ID	Task Name	Duration	Start	Finish	Predecessors	pr 25, '21	May 2, '21	May 9, '21	May 16, '21	May 23, '21	May 30, '21	Jun 6, '21	Jun 13, '21	Jun 20, '21	Jun 27, '21	Jul 4, '21	Jul 11, '21	Jul 18, '21	Jul 25, '21	
1						M	T	W	T	F	S	M	T	W	T	F	S	M	T	W
2	PRE CONSTRUCTION	35 days	5/1	6/18																
3	PO	5 days	5/1	5/6																
4	PERMIT	2 days	5/7	5/10 3																
5	NOC	1 day	5/11	5/11 4																
6	SUBMITALLS	5 days	5/12	5/18 5																
7	APPROVALS	5 days	5/19	5/25 6																
8	FABRICATIONS	20 days	5/24	6/18 7																
9	CONSTRUCTION	28 days	6/21	7/28																
10	MOBLIZE - BARACADES	1 day	6/21	6/21 8																
11	CLEAR -GRUB	3 days	6/22	6/24 10																
12	SITE	23 days	6/25	7/27																
13	SURVEY	1 day	6/25	6/25 11																
14	FOOTER	6 days	6/28	7/5 13																
15	COLUMNS	6 days	7/6	7/13 14																
16	WALL	8 days	7/14	7/23 15																
17	PAINT	2 days	7/26	7/27 16																
18																				
19	FINAL INSPECTION:	1 day	7/28	7/28 17																

Project: OYER PARK-WALL Date: 4/8	Task	Project Summary	Manual Task	Start-only	Deadline
	Split	Inactive Task	Duration-only	Finish-only	Progress
	Milestone	Inactive Milestone	Manual Summary Rollup	External Tasks	Manual Progress
	Summary	Inactive Summary	Manual Summary	External Milestone	

Page 1

RPM GENERAL CONTRACTORS, INC